



**Engineering Cell**  
**Delhi Technological University**  
Shahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/0054/2025-26/Civil

Dated: 17.09.2025

**NOTICE INVITING QUOTATION (Revised)**

The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors/Suppliers up to 03.00 PM on 22.09.2025 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 22.09.2025.

| S.No. | Name of Work   | Estimated Cost (Rs.) | Time Allowed | Last date of Receipt of Quotation |
|-------|--|----------------------|--------------|-----------------------------------|
| 1.    | Providing and Fixing of Safety Net in APJ Hostel and replacement of fly proof mesh in all old Boys Hostel (06 Nos.) at DTU Campus. | 4,96,177/-           | 30 days      | 22.09.2025                        |

**TERMS & CONDITIONS:-**

1. The work shall be carried out as per CPWD specifications/manufacturer's specification.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.
5. Payment shall be made after execution of work.
6. Penalty on account of delay of the work due to any reason (if any) may be imposed @500/- per day or as decided by the Engineer-in-Charge.
7. Any damages/ unforeseen charges during the work shall be borne by contractor. Nothing shall be paid in this account.
8. Water Charges @1% and Electricity Charges @1% shall be deducted from the bill, if any.
9. The lowest contractor will be required to furnish/ submit performance guarantee (P.G.) of 5% (Five Percent) of the quoted value of the work amount within 03 working days from the date of issue of P.G. letter. Thereafter, the work will be awarded and P.G. will be released only after successfully completion of work. In case of non-performance, the same shall be forfeited.
10. All materials should be as per the approved make as decided by the Engineer-in-Charge. Contractor should submit the samples for approval before executing the work.

**Enclosure: Schedule of work & Approved make list.**

*Rajiv*  
17/09/2025  
Executive Engineer

Copy to:-

1. Registrar, DTU
2. COF, DTU
3. Sr. Account Officer, DTU
4. A.E. (Civil)/ J.E. (Civil)
5. DTU website
6. Notice Board.

*Abhishek*  
17/09/25  
A.E. (Civil)

**Schedule of Quantity**

**Name of work:- Providing and Fixing of Safety Net in APJ Hostel and replacement of fly proof mesh in all old Boys Hostel (06 Nos.) at DTU Campus.**

| S. No. | Description Of Items   | Qty.   | Unit | Rate (Rs.) | Amount (Rs.) |
|--------|--|--------|------|------------|--------------|
| 1      | Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete. With 12X3 mm mild steel beading/ flat.  | 130.00 | Sqm  | 1051.75    | 136727.50    |
| 2      | Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to twelve story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judiciously, necessary deduction for scaffolding in the existing item to be done. (No extra payment shall be paid on account of building height) | 600.00 | Sqm  | 285.00     | 171000.00    |
| 3      | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work   | 60.00  | Sqm. | 131.45     | 7887.00      |
| 4      | 18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).  | 140.00 | Sqm. | 442.75     | 61985.00     |
| 5      | Dismantling old plaster/ grit plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead for all height and lift.  | 140.00 | Sqm. | 45.05      | 6307.00      |
| 6      | Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes   | 115.00 | Kg   | 140.85     | 16197.75     |

*Handwritten signature*

|                             |  |       |      |                    |                      |
|-----------------------------|--|-------|------|--------------------|----------------------|
| 7                           | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. | 40.00 | Cum  | 219.35             | 8774.00              |
|                             |  |       |      | <b>Total Rs.</b>   | <b>₹ 4,08,878.25</b> |
|                             | Add GST @18% in place of 12% (factor- 1.0633) on DSR items:  |       |      |                    | ₹ 25.882             |
|                             |  |       |      | <b>Total Rs.</b>   | <b>₹ 4,34,760.24</b> |
|                             | Add cost index @ 7%  |       |      |                    | <b>₹ 30,433.22</b>   |
|                             |  |       |      | <b>Total Rs.</b>   | <b>₹ 4,65,193.46</b> |
| <b>Non-Schedule of Rate</b> |  |       |      |                    |                      |
| 6                           | Providing and fixing Nylon Mesh Balcony Net/Bird Net/Monkey Net (White) 24 Ply tile with Anchor Bolt/Hook Fastener 12 mm and PVC tie clip on existing frame all complete as per direction of Engineer-in-Charge.   | 80.00 | Sqm. | 387.29             | 30983.45             |
|                             |  |       |      | <b>Total Rs.</b>   | <b>₹ 30,983.45</b>   |
|                             |  |       |      | <b>GRAND TOTAL</b> | <b>₹ 4,96,177</b>    |

J.E. (Civil)

J.E. (Civil)

EE/ DTU

74.00

5

### APPROVED MAKES OF MATERIALS (CIVIL)

The Contractor shall obtain prior approval from the Engineer-in-charge before placing order for any specific material or engaging any of the specialized agencies. The Contractor shall make a detailed submission with catalogues and proposed specifications, as well as full details of the works executed by the specialized agency, as specified. Unless otherwise specified, the brands/makes of the material as specified in the item nomenclature, in the list of approved materials attached in the tender and in the particular specifications shall be used in the work. In case of non-availability of the brands specified in the contract the Contractor may be allowed to use alternate equivalent brand of the material by Engineer-in-Charge with the prior approval of NIT Approving Authority subject to submission of documentary evidence of non - availability of the specified brands by contractor. The necessary cost adjustments on account of above change shall be made for the same. The contractor would submit copy of original bills and manufacturer's test certificate for all lots of material procured for the work, payments would be released only for the items for which original bills & manufacturer's test report for the material consumed has been submitted to Engineer-in-Charge. Department shall also get random testing of material from testing Laboratory of its choice.

### LIST OF APPROVED MAKES OF MATERIALS [CIVIL WORK]

| S.NO. | MATERIAL  | MANUFACTURERS NAME  |
|-------|---|---|
| 1.    | CEMENT  | ACC, ULTRATECH, AMBUJA, J.K., LAFARGE, BIRLA, CCI, J.K. SUPER CEMENT  |
| 2.    | REINFORCEMENT STEEL-TMT BARS-FE-500D GRADE              | SAIL, TATA STEEL, RINL, JSW, JSPL   |
| 3.    | STRUCTURAL STEEL SECTIONS                               | SAIL, TISCO, RINL, JSW, JINDAL STEEL & POWER, TATA, APPOLO  |
| 4.    | STRUCTURAL STEEL TUBES/PIPES                            | JINDAL, TATA, APL APOLLO, LLOYDS, SAIL, TATA, JSW   |
| 5.    | LGSF VENDORS  | M/S INTERARCH BUILDING PRODUCTS PVT. LTD., M/S TATA BLUESCOPE STEEL LTD., M/S MGI INDIA PVT. LTD., M/S JSPL, M/S EVEREST INDUSTRIES LTD., M/S WOOTZ BUILDSYS LLP., M/S EPACK POLYMERS.                        |
| 6.    | READY MIXED CEMENT CONCRETE                             | ACC, LAFARGE, ULTRATECH, SHREE, ALCHON, L&T GRASIM, NSCONCRETE, RMC READYMIX (INDIA), SHAILA ENTERPRISES, RDC CONCRETE, TECHNO PRIME RMC PVT LTD, VK READY MIX CONCRETE, ASHTECH, SHRI RAM READY MIX CONCRETE |
| 7.    | ANTI-TERMITE TREATMENT AGENCY                           | PEST CONTROL INDIA LTD, GODREJ PEST CONTROL, CAPITAL PEST CONTROL (INDIA)   |
| 8.    | CHEMICAL TO BE USED FOR 20% E.C.ANTI- TERMITE TREATMENT | DE-NOCIL AND BAYER  |
| 9.    | SHUTTERING PLY  | GREENPLY SHUTTERING PLY, ARCHID SHUTTERING PLY, EURO SHUTTERING PLY   |
| 10.   | SUPERPLASTICIZERS                                       | MC BAUCHEMIE/FOSROC/SIKA/BASF/CHRYSO/VELOSIT/PIDILITE   |
| 11.   | WHITE CEMENT  | BIRLA WHITE, J.K. WHITE   |
| 12.   | AAC BLOCK   | SHREE, INSTABLOCK, BILTECH, MAGICRETE, SIPROX, BIRLA AEROCON, J.K., CLAVECON INDIA PVT. LTD., J.K. LAKSHMI, B.G. SHIRKE/ INDO BHUTANCONSTRUCTION SOLUTION, ULTRATECH XTRALITE,                                |



|     |  |  |
|-----|--|--|
| 13. | BLOCK JOINTING MORTAR                                | JK LAKSHMI, BIRLA AEROCON SMARTFIX, MYK SCHOMBURG, ULTRATECH, FERROUSCRETE, ARDEX  |
| 14. | GLAZED CERAMIC TILES                                 | RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL   |
| 15. | VITRIFIED TILES                                      | RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL   |
| 16. | WALL PUTTY   | JK WHITE, BIRLA WHITE, ASIAN, BERGER, BIRLA, JSW   |
| 17. | PLASTER OF PARIS                                     | JK LAKSHMI, SAKARNI, SHRIRAM, NIRMAN   |
| 18. | GYPSUM PLASTER                                       | SAINT GOBAIN, SAKARNI, J.K. LAKSHMI  |
| 19. | ANCHOR PLUG SOIL/ ROCK ANCHOR                        | BBR, VSL, FREYSSINET   |
| 20. | PORCELAIN TILES                                      | JOHNSON, ASIAN(AGL)  |
| 21. | CHEQUERED TILE                                       | NITCO, ULTRA, UNISTNOE, MODERN   |
| 22. | CC PAVERS, PRECAST CC KERB STONE, CC TILES, RCC SLAB | NITCO, BHARAT, HINDUSTAN, ULTRA, KJS CONCRETE, DURACRETE, KK MANHOLE & COVERS, TERRA FIRMA, PAVER INDIA, DALAL, UNISTONE, CECO, S&S, MOON LIGHT, SWASTIK, ECOCRETE |
| 23. | GRASS PAVER  | UNISTONE, ULTRA, HINDUSTAN, KK, KJS  |
| 24. | SFRC/PRECAST C.C. COVERS                             | KK MANHOLE & COVERS, JAIN, PRAGATI, HINDUSTAN  |
| 25. | FLYASH BRICKS  | POWER BRICK, YBW PROJECT, ASHTECH INDUSTRIES PVT. LTD.   |
| 26. | GLASS MOSAIC TILES                                   | PALLADIO, CORAL, MRIDUL, BISAZZA, MMG TILES  |
| 27. | INSULATION FOR PIPE, RUBBER INSULATION               | KAIFLEX, ARMAFLEX, CAREFLEX, VIDEOFLEX, AFLEX  |
| 28. | COPPER TUBES/ PIPES                                  | RAJCO, MEXFLOW, DELHI METAL, ABC   |
| 29. | READY MIX PLASTER                                    | BIRLA AEROCON, ULTRATECH, RAMCO, WEBER, LATICRETE  |
| 30. | RAISED / CAVITY FLOORING                             | UNI FLOOR, UNITILE INDIA, TATE, ZTFLOOR, ACCESS FLOOR SYSTEMS  |
| 31. | DECK SHEET   | JSW, TATA BLUESCOPE, INTERARCH, JSPL, ROOFCLAD   |
| 32. | SELF-DRILLING SCREWS                                 | TW BUILDEX & BOUSTED, CORROSHIELD, ATUL FATERNERS LTD.   |
| 33. | CPVC PIPE AND FITTINGS                               | PRINCE, SUPEREME, ASTRAL   |
| 34. | LABORTORY SINK                                       | CERA, HINDWARE, JAQUARE  |
|     | PAINTS   |  |
| 1.  | WATER-PROOFING CEMENT PAINT                          | ASIAN, BERGER, DULUX   |
| 2.  | ACRYLIC EXTERIOR PAINT                               | ASIAN (APEX ULTIMA ), BERGER (WEATHER COAT LONGLIFE), DULUX (WEATHER SHIELD POWER FLEX)  |
| 3.  | SYNTHETIC ENAMEL PAINT                               | ASIAN (APCOLITE), BERGER (LUXOL GLOSS), DULUX (DULUX GLOSS)  |

|    |                                 |   |
|----|---------------------------------|---|
| 4. | PLASTIC/ACRYLIC EMULSION PAINT  | ASIAN (ROYAL SHYAN), BERGER (SILK GALMOUR), DULUX (VELVET TOUCH DIAMOND)        |
| 5. | ACRYLIC DISTEMPER               | ASIAN (AQUA LOCK ACRYLIC), BERGER (Bison SUPER), DULUX (MAGIC ACRLYIC)          |
| 6. | CEMENT PRIMER                   | ASIAN (DECOPRIME), BERGER (SOLVENT BASE), DULUX (SOLVENT BASE)                  |
| 7. | WALL PUTTY                      | BIRLA, J.K., JSW  |
|    | SPORTS WORK                     |   |
| 1. | WOODEN FLOORING                 | ASIAN, YONEX, ACTION FLOOR SYSTEM, APEX SPORTS FLOORING                         |
|    | Others                          |   |
| 1. | ALUMINIUM SECTIONS AND FITTINGS | JINDAL ALUMINIUM, NALCO, HINDALCO INDUSTRIES, FINESTA, BHARAT ALUMINIUM COMPANY |
| 2. | FLOAT GLASS                     | SAINT GOBIN, MODI GUARD   |
| 3. | PARTICLE BOARD                  | ACTION TESA, CENTURYPLY, GREENPLY, MERINO, ARCHIDPLY DECOR                      |
| 4. | ROLLER BLINDS                   | VISTA, MAC  |
| 5. | BLOCK BOARD                     | CENTURY PLY, GREENLAM, ACTION TESA, KIT PLY                                     |
| 6. | LAMINATED SHEET                 | MERINO, GREENLAM, CENTURY PLY   |
| 7. | S.S. FITTINGS FOR WOODEN WORK   | HARDWYN, GODREJ, HETTICH  |
| 8. | G.I. SHEET                      | SAIL, TATA, JINDAL, ISPAT, JSW, JSPL  |

The Agency is required to get prior approval of Engineer-in-charge for the make of the material to be used in the work. In case of non-availability of material from these manufacturers, the Hon'ble Vice Chancellor, DTU may allow use of alternative BIS approved manufacturer makes.

Executive Engineer  
Delhi Technological University